

Texas Ancillary Structures Interest Group

Welcome to the annual meeting





### Housekeeping


- Virtual attendees are muted. Submit a message in the Q&A if you have a question.
- In-person attendees, please make sure that you've registered (helps with planning)
- Coffee bar Need to get badge from security desk
- Lunch is off-site
- Restrooms




Texas Ancillary Structures Interest Group



### **Building Safety**








### **Texas Ancillary Structures Interest Group (TASIG)**

Overview: This is a joint owner-industry forum aimed at guiding, advancing and improving ancillary structure aspects such as:







Design

Fabrication

Construction




### **Texas Ancillary Structures Interest Group (TASIG)**

#### Goals:

- Industry feedback, industry education
- Advance design/details/fabrication/construction
- Address procedural and performance issues



### **Texas Ancillary Structures Interest Group (TASIG)**



TASIG Email:

BRG-TASIG@txdot.gov

TASIG Website:

https://www.txdot.gov/insidetxdot/division/bridge/ancillarystructures.html

### 2025 TASIG AGENDA



Time	Topic	Speaker	
9:00 AM	Welcome to TASIG 2025	TXDOT	
9:05 AM	TxDOT Updates on Ancillary Structures	TxDOT	
9:40 AM	Open Discussion		
10:00 AM	Break		
10:20 AM	Research Updates Presentation		
	0-7193: Develop Assessment and Mitigation Guidance for Ancillary Highway Structures with Existing Cracks	UT and A&M	
	0-7192: Develop Performance of Baseplate Connections in COSS and Traffic Signal Structures	TTI	
	0-7236: Development of Standardized LRFD Design Methods for Ancillary Highway Structure Foundations	TxDOT	
11:20 AM	Open Discussion		
11:45 AM	Lunch (11:45am-1pm offsite)		
1:00 PM	Resources	TxDOT	
1:30 PM	Open Discussion		
1:50 PM	Break		
2:10 PM	Shop Drawings	TxDOT	
2:30 PM	Open Discussion		
2:55 PM	Closing Remarks		
3:00 PM	Adjourn		



### **Traffic Safety Division**

Standard Updates

Rafael Riojas, Traffic Engineering Section Director



### **HELP MAKE TEXAS SAFER FOR EVERYONE**

### DRIVE like TEXAN

Kind. Courteous. Safe.





### **ED-25 Sheet Updates**

- Sheets where released April 14, 2025
- These standard sheets may be used immediately and shall be used for all applicable PS&E sets beginning with the October 2025 letting.



### **ED-25 Sheet Updates**

- ED
  - Changed the length of conductors outside of weatherheads to be 18 in. to 36 in. as required by the electric utility.
- ED(1)
  - Clarified RMC minimum burial measurements to 18" below grade or bottom of ground box.
- ED(4)
  - Modified ground box detail to specify concrete without the class.



### **ED-25 Sheet Updates**


- ED(7)
  - Increased the quantity of rebar for underground service foundations to satisfy NEC requirements for concrete-encased grounding electrodes.
- ED(11)
  - Revised foundation detail to remove callouts associated with RMC elbows.
- ED(12)
  - Revised Section A-A detail to show:
    - Conduit entering the ground box on one side;
    - The callout for concrete without specifying the class.



### HMID(2)-25 update


- Sheets where released May 21, 2025
  - Revised the weld in Detail "G". This revision reverts the weld to its original configuration on the support arm [per HMID-03].

### HMID(2)-25 update





### HMID(2)-25 update





# BRIDGE (STRUCTURES)



# **TxDOT Ancillary Structure Standards BRG maintains the** *structural aspects* of:

Standard Description	Standards	Current Design Spec.	Upcoming Design Spec.
High Mast Illumination Assy	HMIP, HMID	LTS-3 (1994)	LTS-6
Roadway Illumination Assy	RIP, RID	LTS-6 (2013)	LRFD-LTS
Overhead Sign Structures	OSB, HOSB, COSS, HCOSS	LTS-3 (1994)	LRFD-LTS
Monotube Sign Structures	MS, MC	LTS-6 (2013)	
Traffic Signal Poles	SP, SMA, DMA, MA, MAC, MAD, TS, LUM, CFA, LMA	LTS-3 (1994)	LRFD-LTS
Wind and Ice Maps	WV & IZ	LTS-3 (1994) & LTS-6 (2013)	LRFD-LTS

https://www.dot.state.tx.us/insdtdot/orgchart/cmd/cserve/standard/toc.htm



# **TxDOT Ancillary Structure Standards BRG maintains the** *structural aspects* **of:**


Special Details	Standards	Current Design Spec.
DMS Attachment Details	DMS-TM & DMS-HZ	LTS-3 (1994)
Connection between concrete column & truss sign support	Upcoming	LTS-6 (2013)
Bridge Railing Sign Mount	SMD(BR)	LTS-6 (2013)
Sign Mounting Details	SMD	LTS-3 (1994)



### **MAINTENANCE**





- Looking at \$1.85B next year for maintenance
- Approximately \$50M per year in signals, illumination, large signs, and ITS
- About \$4M is structural work





### **Pole Attachment Connections**





- License Plate Reader Attachments
- Best practices for attachments?



## HMIP/OHSS Inventory and Inspection Greg Jones, P.E.



August 15, 2025



### **The Need**

Before 2020 - No statewide records of large traffic structures:

- Locations
- Quantities
- Conditions age, damage





### **Contract with MBI**


- Tasks:
  - Inventory, Inspection, Database
- Ancillary Structures:
  - High Masts, Overhead Sign Structures, ITS Poles, Signals
- Sept 2025 End of contract






### **High Mast Poles**

- 2025: Completed HM Inventory
- Over 6000 HM poles
- Structural inspection of 1 in 4






- 2022: Failure of COSS on US 75 in N
  Texas
- 2022: TxDOT Statewide inspection of COSS anchor bolts






- 2022: Failure of COSS on US 75 in N
  Texas
- 2022: TxDOT Statewide inspection of COSS anchor bolts
- 2023: Inspected OHSS in FTW and DAL





- 2022: Failure of COSS on US 75 in N
  Texas
- 2022: TxDOT Statewide inspection of COSS anchor bolts
- 2023: Inspected OHSS in FTW and DAL
- 2024: Completed OHSS statewide inventory





- 2025: NDT of FTW and DAL COSS
- Structures with >2 loose nuts
- 15 of 87 inspected structures had cracks in weld to base plate.
- Up to 5 cracks 1" to 3" long
- Notified Districts



Indication #1 and #2 at Tension End of the Structure



#### **GIS** database

- ArcGIS Online
- On TxDOT ArcGIS Online system
- All data available Sept 2025
- Get account through Service Desk
- Group TxDOT HMI and OSS Inspection Reporting





#### **Next Contract**

- Planned for FY2027
- Add new construction
- Inspect more structures
- May add other structure types

