


Built-up Press-brake Formed Tub Girders



Research Need Statement

- Accelerated bridge construction has evolved significantly, with a focus on minimizing traffic disruption
- Little research in advancing rapid fabrication
- Fabrication of simple steel bridges takes tens of weeks
- Prestressed concrete girders dominate short-span market, but are heavy, often requiring large cranes and special trucking and permits



Not just ABC but ABF

Accelerated Bridge Construction (ABC)

- Dramatic reduction in traffic disruption
- Modest overall time savings

What about Accelerated Bridge Fabrication (ABF)?

- From months to days?

Kit of Parts


- Minimize time for design, shop drawings, and fabrication



Existing Short-Span Steel Solutions

Valmont U-BEAM™

An AASHTO Box Section Flexural Member



Groundbreaking innovation catered to your needs

Valmont U-BEAM™ Use

U-BEAM™ Components


- Press-brake formed steel plate
- Angle braces
- End diaphragm
- Splice plate, bolts & nuts
- Shear studs
- Sole plate

Standard shapes expedite design and drawing process


Functional design

Value-added components cater to each project

Press-Brake-Formed Tub Girders



Folded Steel Plate Girder



Valmont & Investment in PBTG



Valmont Workflows

#1 AASHTO STEEL PLATE MATERIAL

AASHTO 11.3.1.2
AASHTO M270. Made in the USA. Steel Plates and Structural Shapes shall conform to ASTM A709/A709M.



#2 AASHTO FORMING

AASHTO 11.4.3.3 - Bent Plates
Fracture-critical and Non-fracture critical plates and bars shall be cold bent.



#3 AASHTO CAMBERING

AASHTO 11.4.12.2.7
Cold cambering is a customary means of achieving camber... to avoid impact damage to the steel, it's appropriate to introduce bending pressure in a controlled fashion.

#4 AASHTO WELDING AND SHEAR STUDS

AASHTO 11.3.3
Certified Welders and welded stud shear connectors shall satisfy all requirements of the AASHTO/AWS D1.5M/D1.5 Bridge Welding Code related to material, manufacturing, physical properties, certification, and welding.



#5 AASHTO PROTECTIVE COATING

AASHTO 11.3.7
Galvanizing shall be in accordance with AASHTO M 111/M 111 (ASTM A123/A123M)

Built-up Press-brake Formed Tub Girders

Distinct Form:

- Web is the only press brake formed component
- Virtually any tub shape and long spans possible
- No Welding
- Bolted Up Form is internally redundant
- Can be transported loose (webs stack like pringles)
- Transmission Pole Manufacturing Workflows



Longitudinal Stresses
18 9.7 1.3 -7.0 (ksi)



System Redundancy – Twin Box Girder Bridges

UT Austin Tests on Twin Box Girders

- Blast induced Bottom Flange Fracture = 1" deflection under HS20
- Full Web Fracture & Explosive Release from Temp Support = 7" deflection
- Final Static Load Test – Applied Load of 363 kips >5x legal limit



FSEL Test Bridge



Figure 1.7: Second bridge fracture test



Incremental loading




Collapsed bridge

Explosively Induced Fracture & Support Loss


Internal Redundancy – Rob Connor’s Work

Purdue Research Girders Subjected to Flexure

- Built-up sections prevent crack propagation to adjacent
- Cooled to -83°F (lower shelf)
- Driving wedges to force cover plate crack propagation
- No propagation into any component



Test Setup for Fatigue and Strength




Cover Plate Crack Induced by Wedges

Internal Redundancy - Stacked FB's & Through Stringers



Built-up Press-brake Formed Tub Girders

- Piece-wise straight: Camber & Curvature through kinked splices




Research Project


Objectives:

- 1) Design and build 2 demonstration bridges
- 2) Measure behavior of demonstration bridges
- 3) Develop and optimize a kit-of-parts system

Collaboration:



- Bringing new fabrication capabilities to accelerate project delivery



- Steel on the Ground (No Mill Order Step)
- Fabrication on-demand or prefabricated stockpile



Two Demonstration Bridges

Simple Span: 97 ft




Two-span Continuous:
105 ft – 86 ft




Existing Bridges

Simple Span (97 ft)


Built-up Press-Brake Formed Tub Girder Design




Plan



Elevation



Preliminary Design Section







Tub Girder Section

- Tub girders are $\frac{1}{2}$ the weight of prestressed concrete girders
- One less girder line

Two-Span Continuous (105 ft – 86 ft)


Built-up Press-Brake Formed Tub Girder Design




Tub Girder Section

For Both Demonstration Bridges:

Cross-section:



Simple Span and
Two-Span Continuous in
Positive Moment Region




Same Sections for
Both Bridges:

Kit-of-Parts

For Both Demonstration Bridges:

Cross-section:




Two-Span Continuous in
Negative Moment Region

Same Sections for
Both Bridges:

Kit-of-Parts


For Both Demonstration Bridges:

Cross-section:



For Both Demonstration Bridges:

Cross-section:



Press-brake:

transmission pole manufacturers



ASTM A572 Grade 65 /
ASTM A871 Grade 65

CVN's 15 ft-lb @ -20 °F

Photo credit: Delta steel Inc

Mill Test Report

Page 1

Issuing Date : 02/07/2022 B/L No. : 616175 Load No. : 633473 Our Order No. : 195404/1 Cust. Order No. : DFT-67689
 Vehicle No: TTPX 80287 Sold To: DELTA STEEL Ship To: DELTA STEEL INC-FT WORTH SO FRWY
 Specification: 0.6250" x 120.000" x 300.000" 7335 ROUNDHOUSE LN PRIMARY STOCK
 ASTM A572 Grade 65-21e1 Modified Quench and Tempered HOUSTON, TX 77078 9217 S FREEWAY
 FT WORTH, TX 76161

Marking :

Heat No	C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Al(tot)	V	Nb	Ti	N	Ca	B	Sn	Ceq	Pcm
2600561	0.16	1.26	0.008	0.002	0.19	0.10	0.06	0.04	0.01	0.024	0.043	0.002	0.001		0.0013	0.0000	0.008	0.40	0.25

Plate Serial No	Pieces	Tons	Tensile Test					Heat Treat				
			Dir.	Yield (psi)	Tensile (psi)	Elong. % in 2"	Elong. % in 8"	Quench (°F)	Time (min)	Temper (°F)	Time (min)	
2600561-03-4	1	3.19	H-T	89,100	99,900	36.5			1665	27	1250	34

Plate Serial No	Pieces	Tons	Absorbed Energy (Ft-lbs)				Lateral Expansion (in.)				Shear (%)				Min	Temp (°F)	Size		
			Dir.	(ft-lbs) 1	(ft-lbs) 2	(ft-lbs) 3	(ft-lbs) Ave	Min	(in.) 1	(in.) 2	(in.) 3	(in.) Ave	(in.) Min	(%) 1				(%) 2	(%) 3
2600561-03-4	1	3.19	H-L	180.1	171.1	176.1	175.8	15										-20	10mm

175.8 ft-lb @ -20 °F



12400 Highway 43 North, Axis, Alabama 36505, US

Test Certificate

WARNING: This product can expose you to chemicals including nickel and nickel compounds, which are known to the State of California to cause cancer. For more information go to www.P65Warnings.ca.gov.


Form TC1: Revision 4: Date 6 Feb 2019

Customer: INTERNAL USE MOBILE 12400 HWY 43 NORTH AXIS AL 36505			Customer P.O.No.: DFT-71999				Mill Order No. 41-674785-05				Shipping Manifest: AT356856											
			Product Description: ASTM A572(21) 65/M450 CVN15 15 FT.LBS @ -20DEG F/A673-H				Ship Date: 15 May 22 Cert Date: 15 May 22				Cert No: 081046415 (Page 1 of 1)											
			Size: 0.625 X 112.0 X 532.0 (IN)																			
Tested Pieces:			Tensiles:				Charpy Impact Tests				BDWTT											
Heat Id	Piece Id	Tested Thickness	Tst Loc	YS (KSI)	UTS (KSI)	%RA	Elong % 2in 8in	Tst Dir	Hardness	Abs. Energy(FTLB) 1 2 3 Avg				% Shear 1 2 3 Avg				Tst Tmp	Tst Dir	Tst Siz (mm)	BDWTT Tmp %Shr	
E2E127	B15	0.625 (DISCRT)	L	75	87		33	T														
			T	67	83		30	T														
E2E127	B16	0.625 (DISCRT)	L	74	87		36	T														
			T	72	86		35	T														
E2E127	B14	0.624 (DISCRT)	L							127	106	96	110				-22 F	L	10.			
Heat			Chemical Analysis													ORGN						
Id	C	Mn	P	S	Si	Tot Al	Cu	Ni	Cr	Mo	Cb	V	Ti	B	N							
E2E127	.15	1.19	.009	.002	.03	.028	.23	.13	.16	.02	.026	.056	.007	.0001	.0090	USA						

110 ft-lb @ -22 °F


SSAB (Stoddard's work on cold forming)

A709-50/50W specimens formed with 7t, 5t, 3t and 1t bend radii




27 August 1, 2018

Bridge Task For



For Both Demonstration Bridges:


Cross-section:



Bull nose R = 2 3/16"



Airgap



ASTM A871 Grade 65

CVN's 15 ft-lb @ -20 °F

Photo credit: Delta steel Inc


Bridge Details

Lateral Bracing
(L5x3-1/2x3/8)


External Diaphragm
(W30x90)

Internal
Diaphragm


End Diaphragm
(W36x210)




End Diaphragm: W36 x 120




External Diaphragm: W30 x 90




Integral Abutments





Camber: Kinked Splices



Kink Points



Two-Span Continuous: Skewed Diaphragms



SECTION VIEW




Press-Brake Formed Webs




Press-Brake Formed Webs



Full Shop Assembly



Galvanized and Bolted-up at Shop



Transported to Site Fully Bolted Up



Girders Set on Site



Simple Span: Completed July 2023



Two-span Continuous: Completed July 2024



Phase 1 Construction

Lessons Learned & Future Improvements

- Stock material for webs selected based on material certifications to validate bend radii
- For skewed bridges, avoid skewed internal diaphragms
- Further development to limit the number of different pieces
- Optimize Top Lateral Bracing, focus on end regions




Figure 1-12 - a) Usual Top Lateral Bracing (TLB) Layout, b) Optimized TLB Layout (Proposed)




Figure 1-13 - Internal K-frame Details




Figure 3-21 - Instrumentation Layout - Plan View




Figure 3-22 - Instrumentation Layout - Section A-A


Kit-of-Parts

Options for web products:

- Web thickness: 0.5", 0.625", 0.75"
- Web depth: 36" up to 108" in 6" increments
- Bend radius: fixed at $2 \frac{3}{16}$ "

Available flange thicknesses:

- Flat plates: 1", 1.25", 1.5", 1.75", 2"



Acknowledgments

This work was supported by the Joint Transportation Research Program administered by the Indiana Department of Transportation and Purdue University. The contents of this presentation reflect the views of the authors, who are responsible for the facts and accuracy of the data presented herein, and do not necessarily reflect the official views or policies of the sponsoring organizations. These contents do not constitute a standard, specification, or regulation.



Acknowledgments

Business Owner: Stephanie Wagner (INDOT)

Project Advisor: Prince Baah (INDOT)

Principal Investigator: Ashley Thrall (ND)

SAC Members: Vin Bartucca (NSBA), Patrick Conner (LTAP), Andy Fitzgerald (INDOT), Jennifer Hart (INDOT), Amy Huebschman (EMCS, Inc), Jim Lesh (INDOT), Seth Schickel (HNTB), Donald Shaw (INDOT), Ted Zoli (HNTB)

ND Graduate Students: Sherryen Mutoka, Mirela Tumbeva, Yao Wang

HNTB Design Team: Tom Bieneman, Skyler Coombs, Angela Pearl, Ted Zoli

Acknowledgments

NUCOR®

SSAB



DELTA STEEL
SINCE 1963

INFRA-METALS